

No	26.02.24 Date
1 1 V	

EXPRESSION OF INTEREST

The Odisha State Handloom Weavers Cooperative Society Ltd., (boyanka) on behalf of The Orissa State Cooperative Spinning Mills Federation Limited is going for Commissioning and Erection of all machineries along with ancillary electrification and furniture etc. in the premises of Incubation Center, Bhubaneswar. Sealed EOI in two bids "Technical Bid" & "Financial Bid" are invited from reputed firms/contractors having past experience and expertise to execute such type works for Commissioning and Erection of all machineries along with ancillary electrification and furniture etc. in accordance with the EOI documents as follows:

- 1 Name of the work
- : Commissioning and Erection of all machineries along with ancillary electrification and furniture etc. in the premises of Incubation Center, BBSR.
- **2** Earnest money to be deposited
- Rs.30,000.00 (Rupees Thirty thousand) only in shape of DD drawn in favour of the Odisha State Handloom WCS Ltd in any scheduled/commercial bank payable at Bhubaneswar.
- **3** Cost of EOI : document/Processing Fee
- Rs.6,000.00 (Rupees Six thousand) only (Non-refundable)
- **4** Availability of tender in the : website
- www.boyanika.com from **Dt.28.02.2024** to 1.00 PM on **Dt.07.03.2024**
- 5 Last date of submission of sealed EOI in single envelope containing two separate sealed covers (Technical Bid & Financial Bid) superscripting the name of the work on the cover
- Up to 2.00 PM on **Dt.07.03.2024** in the office of the Odisha State Handloom WCS Ltd, Boyan Bhawan PJN Marg, Unit-III, Kharavel Nagar, Bhubaneswar
- **6** Date of opening of EOI
- the Technical bids will be opened in presence of the parties or their authorized representatives at 3 PM on **Dt.07.03.2024** at Conference Hall of Boyanika, Boyan Bhawan, Bhubaneswar and the bidders are required to present a power point presentation regarding their layout design at the time of opening of the Technical Bid.

The bidders are required to display the sample/model of the furniture at the site on Dt.08.03.2024 from 10 A.M to 2 P.M.

The Financial bids in respect of the parties qualified in Technical Bids will be opened at 4 PM on same day i.e. **Dt.08.03.2024** at Conference Hall of Boyanika, Boyan Bhawan, Bhubaneswar.

The interested parties should visit the work site at their own arrangement & ensure about the existing condition of the site, nature of the site, the means of access to the site, the accommodation they may required & in general shall themselves obtain all necessary information as to risks, contingencies & other circumstances which may influence or affect their bid. A bidder shall be deemed to have full knowledge of the site whether he inspect it or not and no extra charges consequent on any misunderstanding or otherwise shall be allowed. The bidder shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work, as necessary and unless otherwise specifically provided for in the contract documents.



- **8** The sealed offers containing Technical Bid (cover-I) and Financial Bid (cover-II) in separate sealed covers to be sealed in a single envelope in conformity with EOI and terms & conditions of the bid document should reach the office of the undersigned by scheduled date & time. The bidders are required to sign the each page of their submitted documents failing which offer shall be treated as canceled.
- 9 The Technical bid must be accompanied with the following documents
- I The cost of EOI documents/Processing fee in shape of Demand Draft.
- **II** EMD in shape of Demand Draft.
- III Detailed layout design in respect of the proposed Commissioning and Erection of all machineries along with showing the details electrification and placement of furniture etc. in the premises of Incubation Center, Bhubaneswar (The bidders are required to present a power point presentation regarding their layout design at the time of opening of the Technical Bid. The bidders are also required to display their sample/model of the furniture at the site on scheduled date & time).
- **IV** Self attested photocopy of GST/GSTIN registration certificate and return copies up to 31st January 2024.
- V Self attested photocopy of PAN and return certificate of income tax for financial year 2020-21, 2021-22 & 2022-23
- **VI** Self attested copy of the Work Order of similar work if any.
- VII Self attested photocopy of valid electrical license from Competent Authority or authorization from any registered electrical contractor having experience in execution of such type of works for execution of electrical work. In case of authorization from any registered electrical contractor, the self attested copy of the valid electrical license of contractor has to be submitted along with proper Memorandum of Undertaking.
- VIII Audited statement of accounts (Balance sheet & Profit Loss account) of the firm for the business showing average turnover not less than 2.00 crore (Rupees two crore) Only for the last 3 financial years (2020-21, 2021-22 & 2022-23) and I.T. return Acknowledgements.
- **IX** EPF registration certificate along with latest return copies.
- The work shall have to be executed within **Dt.09.03.2024 to Dt.18.03.2024** and handover by 5.00 P.M on **Dt.18.03.2024**. The parties having necessary expertise & competency to execute the work with their own arrangement by taking the materials and workers to the site according to the availability and to complete the work within the specified time should only participate in the EOI process.
- The financial bid must be submitted as per the EOI schedule covering/mentioning all the required items of work in befitting manner as per their layout design submitted in Technical Bid. The price quoted should be exclusive of GST but inclusive of all other components like cost of materials, labour charges, transportation charges both for materials and labour, cost towards lifting the materials to the specified work site and any other charges if any. The Financial Bid must be submitted as per prescribed format of schedule of items & quantities, but submission of Financial Bid other than this prescribed format shall be out rightly rejected.
- The Authority is not bound to accept the lowest offer and reserves the right to finalize the EOI according to the selected design, verification of display of sample/model furniture and credibility.
- 13 If the office happens to be closed on the last date of receipt of bids as scheduled, the bids will be received on the next working day at the same time & venue.
- **14** Further any clarification, the interested parties may contact the Executive Engineer of this Apex Society during working hours.
- The authority reserves the right to accept or reject any or all the offers without assigning any reason thereof

Sd/-Managing Director



No	Date
110	

SCHEDULE OF ITEMS & QUANTITIES

S1 No.	Name of the Work	Unit	Qty.	Rate per Unit	Total Amount
Part-	I				
1	Supply & Fitting Sewing Operator Steel & Wooden Bench Size:33"x14"x22"Specification: (1"x1") CR SQ Pipe Frame HeavydutyPVC Bush -4Nos, 17 mm Prelaminated sheets For Top2.0 mm Edge PVC Tape Edge Finish (7 ProcessPowder Coated)complete in all respect as directed by Engineer-in-charge.	Nos.	225.00		
2	Supply to Production Line Table(Size: (8'x2'x2½') SS Arch Type Specification: RYBN (4 way) Bus Bar Chamber (19mmx3mm) Insulated Aluminium Strip Enclose 18 SWG CR Sheet Frame (Lenth8') For Power Circuit, 2"Stainless Steel (202Grade H-39") Post, 1"Stainless Steel (202Grade, W-58") Butterfly Arch, 1¼"x1¼, 1"x1" Bottom Frame With Heavyduty Bush-4 Nos, Lighting Support Pipe (1¼"x1¼" CR Pipe, Lenth-8') -2 Nos, 2.5,1.5,1.0 Sq mm (Finolex) Or (R.R Cable) Wiring For Soucket Lighting Wiring. 17 mm Prelaminated sheetsTop & Bottom 2.0 mm Edge PVC Tape Edge Finish. 20 A 2 Pole Metal Soucket (SG Brand) each 4 Nos. Lighting Switch 5A White (Anchor) each 4 Nos1x25 W LED Tube light set 1 Nos,(Finolex Make) (2 years Warantee) 4Nos (Phosphating & powder coating finish) as directed by the Engineer-in-charge.	Nos.	25.00		
3	Supplying Line Control Panel Specification: 32A Pole MCB 1No, 10A SinglePole, MCB'S 2Nos (Finokex Make) For Lighting & Power Control With RYB Indication Lamp (Phosphating & powder coating finish) as directed by the Engineer-in-charge.	Nos.	9.00		
4	9.6 Mtrsx1.8 Mtrs Cutting Table Specification: (2"x1", 1½"x1½") CR pipe table frame, 17 mm Prelaminated sheets for top and bottom 2.0 mm Edge PVC Tape Edge Finish. (Phosphating & powder coating finish) as directed by the Engineer-in- charge.	Nos.	3.00		
D	Total (A)	T	I		
Part-		NT.	45.00		
5	3'x2½'x3' Helper Table Specification: (1¼"x1¼") CR pipe table frame, 17 mm Prelaminated sheets for top and bottom 2.0 mm Edge PVC Tape Edge Finish Inspection Board 1No.1x25 W LED Tube light set 1 Nos,(Finolex Make) (2 years Warantee) (Phosphating & powder coating finish) as directed by the Engineer-in-charge.	Nos.	45.00		



No	•••••••••••			Date	•••••
6	Supply to Production Line Table(Size : (8'x2'x2½') SS Arch Type Specification : RYBN (4 way) Bus Bar Chamber	Nos.	25.00		
	(19mmx3mm) Insulated Aluminium Strip Enclose 18 SWG CR Sheet Frame (Lenth8') For Power Circuit,				
	2"Stainless Steel (202Grade H-39") Post, 1"Stainless Steel (202Grade, W-58") Butterfly Arch, 11/4"x11/4, 1"x1"				
	Bottom Frame With Heavyduty Bush-4 Nos, Lighting Support Pipe (1 ¹ / ₄ "x1 ¹ / ₄ " CR Pipe, Lenth-8') -2 Nos,				
	2.5,1.5,1.0 Sq mm (Finolex) Or (R.R Cable) Wiring For Soucket Lighting Wiring. 17 mm Prelaminated sheetsTop				
	& Bottom 2.0 mm Edge PVC Tape Edge Finish. 20 A 2 Pole Metal Soucket (SG Brand) each 4 Nos. Lighting				
	Switch 5A White (Anchor) each 4 Nos1x25 W LED Tube light set 1 Nos,(Finolex Make) (2 years Warantee) 4Nos (Phosphating & powder coating finish)				
	as directed by the Engineer-in-charge.	D.T.	10.00		
7	4'x2½'x3' Inspection Table Prelaminated sheets for top and bottom 2.0 mm Edge PVC Tape Edge Finish Inspection Board 1No.1x25 W LED Tube light set 1 Nos,(Finolex Make) (2 years	Nos.	18.00		
	Warantee) (Phosphating & powder coating finish) as directed by the Engineer-in-charge.				
8	8'x4'x3' Common Checking Table Specification: (1¼"x1¼") CR pipe table frame 7 mm Prelaminated sheets for top and bottom 2.0 mm Edge PVC Tape Edge Finish. 2"x1" 1¼"x1¼" MS Pipes (For Lighting	Nos.	12.00		
	Frame) 1x25 W LED Tube light set 4 Nos,(Finolex Make) (2years Warantee0 (7 Process Powder Coated)				
	as directed by the Engineer-in-charge.				
Part-	Total (B)				
1	Heavy Duty Plate Racks For Fabric Storages (Size : 6'x3'x6'- 3Plates)	Nos.	15.00		
	Specification: 2"×1"CR Pipe Frame Outer Frame, 18 SWG CR Sheet For Top, 2"×2" CR Pipe For Legs.(7 Process Powder Coated)				
2	as directed by the Engineer-in-charge. Heavy Duty Plate Racks For Trims Storages	Nos.	12.00		
2	(Size: 6'x3'x6'- 3Plates) Specification: 2"×1"CR Pipe Frame Outer Frame, 18	1105.	12.00		
	SWG CR Sheet For Top, 2"×2" CR Pipe For Legs.(7 Process Powder Coated) as directed by the Engineer-in-charge.				
3	4'×2'×5' (3 Plates) Garment Moving Trolley Specification :1'/4"x1'/4" CR Pipe,6mm Rod Layer Frame 3 Side Covered, Bottom 1.2mm CR Sheet With Nylon Casterd Wheels (Wheels not quarantee) - 4Nos	Nos.	3.00		
	Capacity 350 Kgs(Phosphating & powder coating finish) as directed by the Engineer-in-charge				



No				Date
4	5'x3' Fusing Table (Heavy duty) Specification: (2"x1", 1½"x1½") CR pipe table frame, 17 mm Prelaminated sheets for top and bottom 2.0 mm Edge PVC Tape Edge Finish. (Phosphating & powder coating finish) as directed by the Engineer-in-charge.	Nos.	2.00	
5	Supply to Production Line Table(Size: (8'x2'x2½') SS Arch Type Specification: RYBN (4 way) Bus Bar Chamber (19mmx3mm) Insulated Aluminium Strip Enclose 18 SWG CR Sheet Frame (Lenth8') For Power Circuit, 2"Stainless Steel (202Grade H-39") Post, 1"Stainless Steel (202Grade, W-58") Butterfly Arch, 1¼"x1¼, 1"x1" Bottom Frame With Heavyduty Bush-4 Nos, Lighting Support Pipe (1¼"x1¼" CR Pipe, Lenth-8') -2 Nos, 2.5,1.5,1.0 Sq mm (Finolex) Or (R.R Cable) Wiring For Soucket Lighting Wiring. 17 mm Prelaminated sheetsTop & Bottom 2.0 mm Edge PVC Tape Edge Finish. 20 A 2 Pole Metal Soucket (SG Brand) each 4 Nos. Lighting Switch 5A White (Anchor) each 4 Nos1x25 W LED Tube light set 1 Nos,(Finolex Make) (2 years Warantee) 4Nos (Phosphating & powder coating finish) as directed by the Engineer-in-charge.	Nos.	25.00	
6	Provision for plumbing work works complete and as per direction of Engineer-in-charge.	Nos.	1.00	
7	Provision for compressior complete and as per direction of Engineer-in-charge.	Nos.	2.00	
Total (C)				
1	Grand Total $(A + B + C)$			

Sd/-Managing Director